



Energy Precisions

Engineered hybrid solar · LiFePO₄
lithium storage · Full installation

ACCRA OFFICE

Tel: (+233) 533 611 611

Email: energyprecisions@gmail.com

Address: Haatso, Ecomog, Accra, Ghana

Our only office. Site surveys and installs across Ghana are booked from Accra.

www.energyprecisions.com

HYBRID LITHIUM SOLAR PACKAGES

WITH LiFePO₄ LITHIUM STORAGE

Turnkey packages — sized for Ghana homes & businesses. All prices include supply, mounting, cables, commissioning & monitoring.

Turnkey hybrid packages — six tiers

3 KVA SYSTEM

ESSENTIAL

Approx. connected load ceiling ~2,500 watts

FROM **GHS 54,900**

Best for flats & small homes

- ✓ 3 kVA hybrid inverter (1)
- ✓ 5 kWh LiFePO₄ lithium battery (1)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (5)
- ✓ DC protection, changeover & AC distribution
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

Typical: fridge, TV, fans, 15-20 LED lights, phone/laptop charging, small appliances.

8 KVA SYSTEM

PLUS

Approx. connected load ceiling ~7,500 watts

FROM **GHS 149,000**

Large home or small office

- ✓ 8 kVA hybrid inverter (1)
- ✓ 5 kWh LiFePO₄ lithium batteries (4)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (16)
- ✓ DC protection, changeover & AC distribution
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

2 fridges/freezers, blender, sound system, iron, rice cooker/microwave, 2 AC (1 / 1.5 / 2.5 hp), 30 bulbs, 4 fans, 2 TVs, 3 computers/laptops, printer.

5 KVA SYSTEM

HOME

Approx. connected load ceiling ~3,500 watts

FROM **GHS 89,500**

Popular family home package

- ✓ 5 kVA hybrid inverter (1)
- ✓ 5 kWh LiFePO₄ lithium batteries (2)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (8)
- ✓ DC protection, changeover & AC distribution
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

1 fridge, blender, sound system, iron, rice cooker, 1 AC (1-1.5 hp max), 25 bulbs, 5 fans, 2 TVs, 3 computers/laptops, printer.

10 KVA SYSTEM

PRO

Approx. connected load ceiling ~9,500 watts

FROM **GHS 199,000**

Executive home / boutique business

- ✓ 10 kVA hybrid inverter (1)
- ✓ 5 kWh LiFePO₄ lithium batteries (6)
- ✓ Battery management / monitoring (1)
- ✓ 570W Jinko / Longi solar panels (20)
- ✓ DC protection, dual MPPT where required, changeover
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

2 fridges/freezers, 2 blenders, sound system, iron, heater, rice cooker, 2 AC (1.5 / 2.5 hp), 30 bulbs, 4 fans, 2 TVs, 3 computers/laptops, printer.

15 KVA SYSTEM

COMMERCIAL

Approx. connected load ceiling ~14,500 watts

FROM

GHS 279,000

Guest house • shop • church hall

- ✓ 15 kVA hybrid inverter (1)
- ✓ 5 kWh LiFePO₄ lithium batteries (8)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (28)
- ✓ AC/DC distribution boards & changeover
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

2 fridges/freezers, 2 blenders, sound system, iron, heater, rice cooker, 4 AC (1 / 1.5 / 2.5 hp), 30 bulbs, 4 fans, 2 TVs, 3 computers/laptops, printer.

20 KVA SYSTEM

POWER

Approx. connected load ceiling ~19,500 watts

FROM

GHS 369,000

Hotel wing • office block • multi-tenant

- ✓ 10 kVA hybrid inverters (2, synchronized)
- ✓ 5 kWh LiFePO₄ lithium batteries (10)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (36)
- ✓ AC/DC distribution boards & changeover
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

2 fridges/freezers, 2 blenders, sound system, iron, heater, rice cooker, 5 AC (1 / 1.5 / 2.5 hp), 30+ bulbs, 4 fans, 2 TVs, 3 computers/laptops, printer.

Why Energy Precisions?

Turnkey engineered packages — not guesswork. Every installation includes commissioning, monitoring setup where specified, and electrical protection suited to Ghana site conditions.

WHAT EVERY PACKAGE INCLUDES

- Hybrid inverter (grid + battery backup topology)
- LiFePO₄ lithium storage — daily cycling, longer service life
- Tier-1 PV modules (Jinko / Longi class)
- Roof mounting, DC / AC cabling, earthing & hazard labels
- Changeover / protection — handover-ready boards
- Remote monitoring & battery management as specified per tier
- Installation testing & client handover checklist

BEFORE YOU ORDER

- Site survey may adjust panel count and battery blocks to match your actual load.
- Larger projects receive engineered BOM, load analysis & formal quotation from Energy Precisions.
- Payment: typically 30% deposit · 40% on delivery · 30% on commissioning (negotiable).

THE ENERGY PRECISIONS DIFFERENCE

Site survey first

We confirm roof area, cable routes, and your real load before final bill of materials.

Transparent engineering

Larger jobs receive load analysis, string planning, and itemised quotations from our team.

Competitive turnkey pricing

One price for supply and professional install — easy to compare with piecemeal quotes.

Accra office, Ghana-wide

One Accra base; nationwide site surveys and installs scheduled by appointment.

Warranty & service: Premium LiFePO₄ batteries · 5-year battery warranty (manufacturer) · 2-year workmanship on installation.

Pricing validity: Prices valid until December 2026. Final design confirmed after site survey.

Book a free site assessment

(+233) 533 611 611 ·
energyprecisions@gmail.com ·
www.energyprecisions.com
Haatso, Ecomog, Accra, Ghana