



Energy Precisions

Engineered hybrid solar · LiFePO₄
lithium storage · Full installation

ACCRA OFFICE

Tel: (+233) 533 611 611

Email: info@energyprecisions.com

Address: Haatso, Ecomog, Accra, Ghana

Our only office. Site surveys and installs across Ghana are booked from Accra.

www.energyprecisions.com

HYBRID LITHIUM SOLAR PACKAGES

WITH LiFePO₄ LITHIUM STORAGE

Hybrid solar with lithium backup (grid + generator ready). Turnkey supply, mounting, protection, commissioning & monitoring for Ghana homes and businesses.

Turnkey hybrid packages — six tiers

6.5 KVA SYSTEM

ESSENTIAL

Approx. connected load ceiling ~5,500 watts

FROM **GHS 140,900**

Entry tier · flats & small homes

- ✓ 6.5 kVA hybrid inverter (1)
- ✓ 16 kWh LiFePO₄ lithium battery (1)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (15)
- ✓ DC protection, changeover & AC distribution
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

Fridge, TV, standing fans, router, 15–20 LED lights, phone and laptop charging, blender or kettle (one at a time). No air conditioning — add a higher tier for AC.

8 KVA SYSTEM

HOME

Approx. connected load ceiling ~6,800 watts

FROM **GHS 190,900**

Popular family home

- ✓ 8 kVA hybrid inverter (1)
- ✓ 16 kWh LiFePO₄ lithium batteries (2)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (19)
- ✓ DC protection, changeover & AC distribution
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

Fridge, rice cooker, blender, iron (staggered), 1 split AC (1–1.5 hp), 25 LED bulbs, 4–5 fans, 2 TVs, home Wi-Fi, 2–3 laptops or computers, printer.

10 KVA SYSTEM

PLUS

Approx. connected load ceiling ~8,500 watts

FROM **GHS 229,900**

Large home or small office

- ✓ 10 kVA hybrid inverter (1)
- ✓ 16 kWh LiFePO₄ lithium batteries (3)
- ✓ Battery management / monitoring (1)
- ✓ 570W tier-1 solar panels (23)
- ✓ DC protection, changeover & AC distribution
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

2 fridges or fridge + freezer, rice cooker or microwave, blender, iron (staggered), up to 2 split AC (1–1.5 hp, not together on full cool), 30 LED bulbs, 4–5 fans, 2 TVs, small office (PCs, printer, router).

12 KVA SYSTEM

PRO

Approx. connected load ceiling ~10,200 watts

FROM **GHS 280,900**

Executive home · boutique office

- ✓ 12 kVA hybrid inverter (1)
- ✓ 16 kWh LiFePO₄ lithium batteries (4)
- ✓ Battery management / monitoring (1)
- ✓ 570W Jinko / Longi solar panels (28)
- ✓ DC protection, dual MPPT where required, changeover
- ✓ Mounting structure (roof)
- ✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

2 fridges/freezers, kitchen blender, rice cooker, iron and heater (staggered), 2–3 split AC (1–1.5 hp — alternate with kitchen peaks, not all on full cool), 30+ LED bulbs, 4–5 fans, 2–3 TVs, home office or shop POS and computers.

Packages (continued)

15 KVA SYSTEM

Approx. connected load ceiling ~12,800 watts

COMMERCIAL

FROM

GHS 344,900

Guest house • shop • church hall

✓ 15 kVA hybrid inverter (1)

✓ 16 kWh LiFePO₄ lithium batteries (5)

✓ Battery management / monitoring (1)

✓ 570W tier-1 solar panels (35)

✓ AC/DC distribution boards & changeover

✓ Mounting structure (roof)

✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

Several guest rooms, commercial fridge, kitchen appliances (staggered), up to 4 split AC (1–1.5 hp) with load management, sound system, reception PCs, security and corridor lighting, small water pump or booster (if within survey load).

20 KVA SYSTEM

Approx. connected load ceiling ~17,000 watts

POWER

FROM

GHS 447,900

Hotel wing • office block • multi-tenant

✓ 10 kVA hybrid inverters (2, synchronized)

✓ 16 kWh LiFePO₄ lithium batteries (6)

✓ Battery management / monitoring (1)

✓ 570W tier-1 solar panels (46)

✓ AC/DC distribution boards & changeover

✓ Mounting structure (roof)

✓ Cables, MC4, earthing & commissioning

TYPICAL LOADS

Multiple guest-room AC (1–1.5 hp, staggered across rooms), commercial kitchen peaks, laundry alternated with AC, fridges, IT/ server room on dedicated circuit, event or hall lighting — engineered load schedule on survey.

Why Energy Precisions?

Turnkey engineered packages — not guesswork. Every installation includes commissioning, monitoring setup where specified, and electrical protection suited to Ghana site conditions.

WHAT EVERY PACKAGE INCLUDES

- Hybrid inverter (grid + battery backup topology)
- LiFePO₄ lithium storage — daily cycling, longer service life
- Tier-1 PV modules (Jinko / Longi class)
- Roof mounting, DC / AC cabling, earthing & hazard labels
- Changeover / protection — handover-ready boards
- Remote monitoring & battery management as specified per tier
- Installation testing & client handover checklist

BEFORE YOU ORDER

- Hybrid systems — solar plus lithium backup with ECG/grid and generator; not standalone off-grid unless engineered on survey.
- Connected load ceilings assume ~0.85 power factor; stagger AC, iron, and heater — do not run all heavy loads at once.
- Panel counts sized to each inverter at max DC/AC ratio (1.3) with 570 W modules — full load, not load-diversity reduction.
- Storage uses stocked 16 kWh LiFePO₄ modules; site survey confirms module count and backup hours.
- Larger projects receive engineered BOM, load analysis & formal quotation from Energy Precisions.
- Payment: typically 30% deposit · 40% on delivery · 30% on commissioning (negotiable).

THE ENERGY PRECISIONS DIFFERENCE

Site survey first

We confirm roof area, cable routes, and your real load before final bill of materials.

Transparent engineering

Larger jobs receive load analysis, string planning, and itemised quotations from our team.

Competitive turnkey pricing

One price for supply and professional install — easy to compare with piecemeal quotes.

Accra office, Ghana-wide

One Accra base; nationwide site surveys and installs scheduled by appointment.

Warranty & service: Premium 16 kWh LiFePO₄ batteries · 5-year battery warranty (manufacturer) · 2-year workmanship on installation.

Pricing validity: Prices valid until December 2026. Final design confirmed after site survey.

Book a free site assessment

(+233) 533 611 611 ·
info@energyprecisions.com ·
www.energyprecisions.com
Haatso, Ecomog, Accra, Ghana